



Cabinet Construction

From top to bottom, only quality material is used

1. The side panels are 3/4" thick hardwood plywood.

- Side panels are called "end panels."
- Several options available, including:
 - Flush beaded
 - Flush construction

2. The back panel is 1/4" thick hardwood plywood.

- Options include:
 - 3/8" thick beaded back panel
 - 3/4" thick flush back panel

3. The top and bottom are 1/2" thick hardwood plywood.

4. The interior is natural birch melamine.

- Options include:
 - Veneer that is stained to match the exterior color
 - Natural maple veneer

5. Shelves are 3/4" thick hardwood plywood.

- The shelves in base cabinets are two-thirds deep.
- Full depth shelves are available in base cabinets.

6. The toe kick is fully enclosed.

